

# Alternative Tiles

For tiles with more fizz!

## UNDERFLOOR HEATING

### Important please read carefully

The heating mat or cable should be tested by the tiler during tiling to demonstrate the mat is capable of working after the tiling is complete. At Alternative Tiles we test the mat and probe ourselves prior to you collecting your under floor heating kit for our peace of mind.

Make sure the electrician connects the wires up correctly, not every kit is the same. It is not uncommon for electricians to wire the probe up incorrectly and fusing it - this renders the probe useless, dishonest electricians have been known to wire it up correctly afterwards and claim it's faulty to the customer.

The electrician is required to fill out the warranty book to agree that it has been tested and works. Without this the warranty is void as this is designed to be installed professionally by qualified people.

Underfloor heating should not be turned on for at least 2 weeks after the tiling is completed then the temperature should be increased from 18-20 degrees floor temperature to around 28 over the course of 7 days. Once this cycle has been done the UFH can be used normally from then onwards.

The system we supply is extremely reliable. We have very few problems however the problems we do encounter are due to errors during installation, we are trying to prevent this with this information. We can recommend an excellent electrician who understands UFH if you require us to do so, ask for his card or details.